BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/01/2015-16 Dated: 04-01-2016

APPROVED TENDER SCHEDULE –'B'

Item No: 34

Name of Work:-Maintenance of Existing borewells and supply of water through water tanker at yelahanka old town area in ward No- 02 of yelahanka Sub division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri G MUNIRAJU	
				Rate	Rate in Words
1	Supply of drinking water through water tanker at yelahanka old town areas in ward no - 02 as per BWSSB approved rates	No	540.00	360.00	Rupees three hundred sixty only
2	Lifting of Submersible Pump set (P,46/I.10.3.21 RDED SR (2002-03)	No	3.00	850.00	Rupees eight hundred fifty only
3	Transportataion of pumping machineries (P.46/I.103)RDED SR (2002-03)	No	3.00	900.00	Rupees nine hundred only
4	**A) Repairs to Motor:Rewinding of submersible pump sets with copper insulation wire of suitable gauge as per ISI specification with guarantee of 6months. RDED SR (2002-03)P NO.39/ I,NO.A)**				
	a) -Do - above 3HP upto 5HP	No	2.00	2500.00	Rupees two thousand five hundred only
	b) -Do - above 5HP upto 10HP	No	1.00	3700.00	Rupees three thousand seven hundred only
	(Above 5HP upto 10HP add Rs.115/- for every 1/2 HP)				
	B) Replacement of Motor Parts:				
5	Above 5HP Stator (with one year Gurantee) P.No.40/Ino.C(2)RDED SR (2002-03)	No	3.00	5050.00	Rupees five thousand fifty only
6	Above 5HP Rotor (with one year Gurantee) P.No.40/I No.C(2)RDED SR (2002-03)	No	3.00	4700.00	Rupees four thousand seven hundred only
7	Upper Flange P.No.40/I No.3 RDED SR (2002-03)	No	3.00	350.00	Rupees three hundred fifty only
8	Lower Housing P.No.40/I No.4 RDED SR (2002-03)	No	3.00	650.00	Rupees six hundred fifty only
9	Lower Flange P.No.40/I No.5 RDED SR (2002-03)	No	3.00	350.00	Rupees three hundred fifty only
10	a) Carbon Housing P.No.40/I No.7A RDED SR (2002-03)	No	3.00	475.00	Rupees four hundred seventy five only
11	b) Thrust bearing block assembly complete with Segment bearing pad P.No.40/I No.7B RDED SR (2002-03)	No	3.00	1150.00	Rupees one thousand one hundred fifty only
12	c) Tip Carbon /Ferrodo pading P.No.40/I No.7C RDED SR (2002-03)	No	3.00	150.00	Rupees one hundred fifty only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri G MUNIRAJU	
				Rate	Rate in Words
13	Bearing (Gun metal)Centrifugal cast Aluminium Bronze, bearing bush P.No.41/I No;9 RDED SR (2002-03)	No	3.00	400.00	Rupees four hundred only
14	Motor Base with pin P.No. 41/ I No.11 RDED SR (2002-03)	No	3.00	475.00	Rupees four hundred seventy five only
15	Re-erection charges of pumping machineries including overhauling and painting P.No.41/I No 13,RDED SR (2002-03)	No	3.00	950.00	Rupees nine hundred fifty only
16	Labour Charge (overhauling Motor only) P.No.41/ I No.15 RDED SR (2002-03)	No	3.00	550.00	Rupees five hundred fifty only
17	C) Replacement of pump parts: The following main components of submersible pump sets requiring replacement Pump bowls P.No.39 / I No B1 RDED SR (2002-03)	No	3.00	700.00	Rupees seven hundred only
18	Intermediate piece (I.P) with IP leaded bronze bush P.No. 44/ I No.B2 RDED SR (2002-03)	No	3.00	450.00	Rupees four hundred fifty only
19	Oil seal P.No. 44/ I No.B3 RDED SR (2002-03)	No	3.00	125.00	Rupees one hundred twenty five only
20	Oil seal steel bush P.No. 39/ I No.B4 RDED SR (2002-03)	No	3.00	150.00	Rupees one hundred fifty only
21	Guide vane Pno 39/I No B5 RDED (2002-03)	No	4.00	175.00	Rupees one hundred seventy five only
22	Impeller (shell moulded with aluminium and Bonze) P No 39/ I no B6 RDED SR 2002-03	No	4.00	425.00	Rupees four hundred twenty five only
23	a) Discharge outlet (D.O) Bearing D.O Steel Bush P.No. 39/ I No.B7 RDED SR (2002-03)	No	3.00	445.00	Rupees four hundred forty five only
24	b)D.O Bearing P.No. 39/ I No.B7 RDED SR (2002-03)	No	4.00	285.00	Rupees two hundred eighty five only
25	Steel bush (D.O) steel bush) P.No. 39/ I No.B8 RDED SR (2002-03)	No	4.00	150.00	Rupees one hundred fifty only
26	Allen Screw P.No. 40/ I No.9 RDED SR (2002-03)	No	4.00	25.00	Rupees twenty five only
27	Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages) P.No. 40/ I No.10 RDED SR (2002-03)	No	4.00	950.00	Rupees nine hundred fifty only
28	Pump key (Stainless steel) P.No. 40/ I No.11 RDED SR (2002-03)	No	4.00	125.00	Rupees one hundred twenty five only
29	Pump coupling (stainless steel) P.No. 40/ I No.12RDED SR (2002-03)	No	4.00	250.00	Rupees two hundred fifty only
30	Non - Return valve (NRV) assembly complete with rubber 'O' Ring P.No. 40/ I No.13RDED SR (2002-03)	No	4.00	1350.00	Rupees one thousand three hundred fifty only
31	Cabble guard P.No. 40/ I No.14RDED SR (2002-03)	No	4.00	150.00	Rupees one hundred fifty only
32	Strainer P.No. 40/ I No.15RDED SR (2002-03)	No	4.00	150.00	Rupees one hundred fifty only
33	Providing and fixing 50 mm dia heavy duty coller SE RDED Approved rate	No	4.00	130.00	Rupees one hundred thirty only
34	KSRB 2-1.1:Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications (P.NO - 5, I.NO - 2.1, PWD SR 13-14)	Cum	378.00	283.02	Rupees two hundred eighty three and paise two only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri G MUNIRAJU	
				Rate	Rate in Words
35	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation Etc., Page No.12 item No.3.4.2 b PRED SR 2010-11.	Rmtr			
	75mm dia 6 KSC PVC pipe		200.00	157.00	Rupees one hundred fifty seven only
	63 mm dia 6 KSC		500.00	112.00	Rupees one hundred twelve only
36	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications (P.NO - 6, I.NO - 2.11, PWD SR 13-14)	Cum	378.00	76.32	Rupees seventy six and paise thirty two only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.